SL No.	Specification	UNIT	No	L	B	D	Quantity	RATE (in Rs)	AMOUNT (in Rs)
89	KSRRB M800-7. Painting:-Providing and applying two coats of ready mix paint of approved brand after through cleaning of surface to give an even shade complete as per specifications. MORTH Specification No. 803 (As directed by the engineer in charge								
	Not Operated								
90	KSRRB M800-10. Painting new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade complete as per specifications. ("ii) English and Roman - Hyphen and the like not to be measured and paid for MORTH Specification No. 801 As directed by the engineer in charge								
	Not Operated								
91	KSRRB M800-4. Direction and Place Identification Signs with size more than 0.9 sqm Size Board:-Providing and erecting direction and place identification retro- reflectorised sign as per IRC :67 made of high intensity grade sheeting vide clause 800.1.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete45 cm x 45 cm x 60 cm, 60 cm below ground level as per approved drawing complete as per specifications. MORTH Specification No.801 (PWD BCSR 2014-15, P-177, I-24.4) Using Type IV sheeting,As directed by the engineer in charge								
	Not Operated								
92	KSRB 4.2.10 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs, with 12mm and down size graded granite metal coarse aggregates @0.5175cum and fine aggregtes @ 0.345cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications. Specification No. KBS 4.1, 4.6 (P W D BCSR 2014-15, P-14 I-4.19)								
	Not Operated								
93	KSRB 4-6.10 Providing and removing centering, shuttering, strutting, propping etc., forchajjas, corbels etc., including edges including cost of all materials, labour complete as per specif icaiton. Specification No. KBS 4.6.2 etc., As directed by the engineer in charge								
	Not Operated								
94	Supplying and fixing pressed steel door frames size 125 x 65 mm manufactured from 1.25 mm thick carbon steel or imported steel strips with mitred joints of 90 degree, for door openings and shutters made out of seasoned Honne wood, styles of 30 mm, thick witk lockrail of 160 mm, width top and side rails of 100 mm, width and bottom rails of 250 mm width and panel filling with 12 mm thick particle board of exterior grade bonded with phenol formal dehide resin and the shutter shall be rot proof, vermin proof, heat resistant guaranteed against shrinkage, warpage and such othjer defects for a period of 3 years. This shall be as per approved drawings, specification and direction including cost of conveyance, manufacturing, painting with enamel paint 2 coats over primer coat, cost of labour for all items of work, machinery, equipment and all other incidental charges with all lead, lift, loading and unloading etc., complete. The Hollow portion of the frame to be filled with cement concrete 1:2:4 · As directed by the engineer in charge								
	Not Operated								

Scanned by CamScanner

SL No.	Specification	UNIT	No	L	B	D	Quantity	RATE (in Rs)	AMOUNT (in Rs)
95	KSRB 7.10 : Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using double track window frame section of size 61.85x31.75mm. with 1.2mm thick,bottom section weight 0.695 kg/m, sides and top sections 1.3 mm. thick weight 0.659 kg/m; and shutter comprising top and bottom section of size 40mmx18mm, 1.25mm thick 0.417 kg./m; shutter outer side 40mmx18mm, 1.25mm.thick weight 0.417 kg/m, shutter interlock section 40mmx26.7mm, 1.1mm thick, weight 0.469 kg/m. the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; and providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted in the assembled frame stiffened with end clips at corners angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be with necessary steel screws, raul plugs, or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar, aluminium sections pretreated for removal of any Specification No. KBS using aluminium section anodized to 12 - 15 microns As directed by the engineer in charge								
	Not Operated								
96	Providing vitrified tiles 60x60cms of approved make, shade and size for flooring, laid on a bed 12mm thick cement mortar 1:3 mix, flush pointing using white cement using color pigment, including cost of materials, labour, complete as per specifications As directed by the engineer in charge								
	Not Operated								
97	Supplying and wiring adopting loop system in existing PVC Conduit /casing caping using copper PVC insulated multi strand 2x1.5 sqmm copper wire with a 6Amps flush type SP control switch shall be fixed on the existig plastic/gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block.complete for each outlet. As directed by the engineer in charge								
	Not Operated								
98	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, culverts, watersupply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil; clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. Specification No. KBS 2.1 (a) / 2.3.5 (P W D BCSR 2014-15, P-5 I-2.3)								
	Not Operated								
99	KSRB 5.4-4 : Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:4 , edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, scaffolding, curing complete as per specifications. KBS 5.1.13 (P W D BCSR 2014-15, P-23, I-5.13)								
	Not Operated								
100	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons.As directed by the engineer in charge								
	Not Operated								

Scanned by CamScanner

SL No.	Specification	UNIT	No	L	B	D	Quantity	RATE (in Rs)	AMOUNT (in Rs)
101	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specificaitons. As directed by the engineer in charge								
	Not Operated								
102	Earthwork excavation for pipeline trenches including depositing on bank upto a lead of 50 mtrs. Including shoring and strutting, danger lighting and using sight rails and boning rods at every 100 mtrs. Wherever necessary as directed in the following strata. By Manual means. In Hard soil As directed by the engineer in charge								
	Not Operated								
103	Providing and installing at site of work P.V.C. pipes of 6 kg./sqcm 63mm dia including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. complete. As directed by the engineer in charge								
	Not Operated								
104	Refilling the basement and pipeline trenches with selected available earth from trench excavation including watering, Consolidation in layers of 15 cm thick including disposing of the surplus earth with a lead of 200 meters. As directed by the engineer in charge								
	Not Operated								
105	Cleaning of borewells including yield testing of Borewell either using slow or fast Rig for not more than 2 hours at the finali depth with a minimum working of 2 hours continuously with air compressor or suitable pump as per specification including the cost of consumables etc ., complete As directed by the engineer in charge								
	Not Operated								
106	Logging/Scanning of Borewell at any depth continuously with the help of logger unit including the cost of transportation charges, crew charges, stationery charges and cost of consumables etc., As directed by the engineer in charge								
	Not Operated								
107	Hydrofacturing of 146 mm to 152 mm dia Borewell by using Hydrofacturing Unit using single packer with minimum of two fractures including transportation of unit supporting vehicle, crew charges, cost of consumables and yield testing of Borewell one hour at once before fracturing and the other after fracturing with in a radius of 50 Kms from taluk head quarters including supplying necessary water for fracturing etc., complete.As directed by the engineer in charge								
	Not Operated								
108	Yield Testing of Borewell at final depth with a minimum of 10 hours continuously with the help of pump Testing Unit including the cost of transportation charges, crew charges and cost of consumables. As directed by the engineer in charge								
	Not Operated								
109	Providing and fixing heavy duty galvanised iron pipe 50mm dia nominal bore with fittings including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. As directed by the engineer in charge								
	Not Operated								

Scanned by CamScanner

SL No.	Specification	UNIT	No	L	B	D	Quantity	RATE (in Rs)	AMOUNT (in Rs)
110	Supply and delivery at site brand new submersible motor with pumpset texmo / innoval / Lubi / Sabar / Atlanta / Calamal / make suitable for vertical installation in 150 mm dia borewell comprising of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for operation of 6HP/4.5KW 14 stage AC supply fitted with required accessories such as suction, casting suction strainers sand guard Non-Return valve etc.. complete. As directed by the engineer in charge								
	Not Operated								
111	Erection of pumpset including aligning and balancing with all necessary erection materials and labour including supply and erection of one pair supporting clamps, one borewell cap, cable clips with bolt, nuts, valves gauges etc., involved in the job (necessary GI pipe and specials will be supplied by the board at the site free of cost).As directed by the engineer in charge								
	Not Operated								
112	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100 Volts as per IS-694:1990 & conforming to GTP of GROUP-A 3C X 2.5 sq.mm As directed by the engineer in charge								
	Not Operated								
113	Supplying fully automatic star-delta starter unit push button type with suitable wires, 3 contactors, one adjustable thermal timer mounted on a common base plate held in steel enclosure for use on 400/440 volts 3 phase and wired after fixing to the existing wooden board for motor. As directed by the engineer in charge								
	Not Operated								
114	Supplying and fixing polished wood board made of not less than 15mm thick plank on both sides of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs srews 20" X 20" X 2.5" As directed by the engineer in charge								
	Not Operated								
115	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers. 100Amps As directed by the engineer in charge								
	Not Operated								
116	Supplying of multi function digital meter with three line back light LCD type display for voltage, Current,Frequency,Power,power factor, KVA, KWH, KVAR suitable for 3 phase 4 wire LT network with IP 64 degree of protection and completely wired as required with communication port and class 0.5s accuracy As directed by the engineer in charge								
	Not Operated								

Scanned by CamScanner

SL No.	Specification	UNIT	No	L	B	D	Quantity	RATE (in Rs)	AMOUNT (in Rs)
117	Suppling, fixing,wiring, earth electrode for grounding conduits, I.C. cutouts and other equipments on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3 of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122mm dia As directed by the engineer in charge								
	Not Operated								
118	Supplying of 1.1 KV LT UG cable having aluminium conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part- 1:1988 & confirming to GTP of GROUP-A (P W D ESR 2014-15, P-55 I-7.4.4) 4 core 16 sqmm.As directed by the engineer in charge								
	Not Operated								
119	KSRB13-3.6 : Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 50mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.14 / 13.6 As directed by the engineer in charge								
	Not Operated								
120	KSRB13-4.2 : Making connection of G.I distribution branch with G.I main of 50 to 85mm. and 100 to 150 nominal bore, including cutting and threading the pipes, providing and fixing Tee, nuts, labour for all item of works, testing and HOM of equipments complete as per specifications. As directed by the engineer in charge								
	Not Operated								
121	KSRB13-6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. As directed by the engineer in charge								
	Not Operated								
122	KSRB13-7.2-4 : Providing and fixing in position 50mm nominal bore non-return valve vertical type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification As directed by the engineer in charge								
	Not Operated								
123	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete. As directed by the engineer in charge								
	Not Operated								
124	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1(a) / 2.3.1 As directed by the engineer in charge								
	Not Operated								

Scanned by CamScanner

SL No.	Specification	UNIT	No	L	B	D	Quantity	RATE (in Rs)	AMOUNT (in Rs)
125	Providing and laying flooring using prepolished, water cut/ gang saw 19mm thick Raw silk / Black pearl granite of width not less than 900 mm granite laid over bed of 20mm thick 1:4 cm & jointed with neat cement slurry mixed with pigment to match shade of granite slabs including laying POP on finished surface and cleaning the surface. including the cost of all materials and labours etc., complete as per specification As directed by the engineer in charge								
	Not Operated								
126	Providing half nosing for 20mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work. HOM of equipment etc., complete as per specification As directed by the engineer in charge								
	Not Operated								
127	Providing Children Play two Seater Standard Swing Equipment: This swing consist of 2 Nos. seats of solid metal seats powder coated of size-500mmx250mmx16 SWG supported by MS chains of length 1.8 mtrs, each seat is suspended by 1 line of chain. The chains are supported by circular housings with bearing from which the chain is suspended. The main beam is of 50mm MS 'A' Class pipe. Size of MS chain 30mmx20mmx5mm thick, the length of the main beam is 2.40 mtrs and height 2.00 mtrs. The 2 Nos. of cost iron heads. Four footing are in 42mm pipes. All pipes are of ISI grade. All the pipes are painted with two coats of super set paint over a coat of protective zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4 curing etc., complete with all lead, lift, loading, unloading and other incidental charges and as per the drawing and specification and direction of the Engineer in charge of the work.								
	Not Operated								
128	Providing Children Play Standard Spring Duck Equipment: The system consists of an FRP coloured duck rocking on a 10mm dia heavy duty coiled spring including fixing the play equipments in CC 1:2:4 curing etc., complete with all lead, lift, loading, unloading and other incidental charges and as per the drawing and specification and direction of the Engineer in charge of the work.								
	Not Operated								
129	Providing and fixing FRP slide of width 2 ft. and length 9 ft. and height 5 ft. with a platform of 2ft. x 2 ft. Aluminium chequered plate, steps made of G.I. sheet 4" with thread metallic and powdered coated including fixing the play equipments in CC 1:2:4 curing etc., complete with all lead, lift, loading, unloading and other incidental charges and as per the drawing and specification and direction of the Engineer in charge of the work.								
	Not Operated								
130	Providing and spreading of sand, As directed by the engineer in charge								
	Not Operated								
131	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH -100/ Chapter 1 (P W D BCSR 2014-15, P-130, I-17.1)								
	Not Operated								

Scanned by CamScanner

SL No.	Specification	UNIT	No	L	B	D	Quantity	RATE (in Rs)	AMOUNT (in Rs)
132	KSRRB M100-4.1. Cost of Haulage Excluding Loading and Unloading MORTH -100/ Chapter I Case-I : Surface Road (P W D BCSR 2014-15, P-130, I-17.1)								
	Not Operated								
133	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(b) / 2.3.5 (P W D BCSR 2014-15, P-5 I-2.3)								
	Not Operated								
134	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2 (P W D BCSR 2014-15, P-15, I-4.28)								
	Not Operated								
135	KSRB 4-6.6 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for columns, pillars, piers, post and struts, circular or curved in plan including cost of all materials, labour complete as per specificaiton. Specification No. KBS 4.6.2 (P W D BCSR 2014-15, P-16, I-4.33)								
	Not Operated								
136	KSRB 4-6.7 :Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2 (P W D BCSR 2014-15, P-16, I-4.35)								
	Not Operated								
137	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specificaitons for heights more than 3.50m from ground level. Specification No. KBS 4.6.2 (P W D BCSR 2014-15, P-15, I-4.29.2)								
	Not Operated								
138	Providing and fixing M.S. Hand railing for Balcony with 50mm dia. M.S. hollow pipe of 14 gauge, welded to 20mmx20mm M.S. square rod placed vertically, spaced at 100mm at regular intervals of 600mm. These vertical rods laterally tied to 3 horizontal rods spaced at equal interval. These assembly is fixed to concrete by using expansion bolts and welding the same to reinforcement bars and making good the surface. All the joints and sections hould be cut to length, welded and grinded wherever necessary etc., complete . The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, etc., complete as per specification and drawing.(P W D BCSR 2014-15, P-42, I-7.35)								
	Not Operated								

Scanned by CamScanner

SL No.	Specification	UNIT	No	L	B	D	Quantity	RATE (in Rs)	AMOUNT (in Rs)
139	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. with primer (P W D BCSR 2014-15, P-42, I-7.35)								
	Not Operated								
140	KSRB 15-18.3 : Providing and applying enamel metal paint one coat (excluding priming coat) on previously painted steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. (P W D BCSR 2014-15, P-117, I-15.75)								
	Not Operated								
141	Providing and fixing Polyethylene water storage tank (P W D BCSR 2014-15, P-XXV, I-691, Code-0302)								
	Not Operated								
142	KSRB13-3.7: Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 15mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.14 / 13.6 (P W D BCSR 2014-15, P-87, I-13.16)								
	Not Operated								
143	KSRB13-6.3-7 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.6 / 13.3 (P W D BCSR 2014-15, P-89, I-13.38)								
	Not Operated								
144	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregtes @ 0.56cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation,plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P W D BCSR 2014-15, P-13, I-4.7)								
	Not Operated								
145	Providing & Fixing Polished grey granite slab benches of size 5 feet width of seating slab with bottom slab of 75mm thick with 1.50 ft with back rest slab of 50mm thick with 1.50ft depth side and slab of 100mm thick 2.50ft height including bull nosing of all indges including fixing in CC 1:2:4 including loading and unloading and with all lead and lift etc, complete and excecuting the work as per the directions of the engineer in charge of the work. CE approved Rate								
	For park	Nos	25				25	11183.0	279575.00
146	Providing and fixing granite benches, with three line dressing, ornamental design with two groves and three bull nose finishing the sides faces of the seating slab of 75mm thickness, resting on two vertical slabs similar, ornamental dressed with peepul leaf shaped groove cutting on outer surface of the legs fixed in concrete bed including cost of all materials, transportation, labour, curing complete as per drawing and directions of Engineer-in-charge CE approved Rate								
	Not Operated								

Scanned by CamScanner